City of OREGON Ohio

FAX

Department of Public Service
5330 Seaman Road
Oregon, Ohio 43616
Phone: (419) 698-7047
Fax: (419) 691-0241

To:	Plan Holders
From:	City of Oregon Department of Public Service
Date:	November 19, 2018
Project:	Annual Waterline Replacement – Homestead Subdivision and Worden Road
Re:	Addendum No. 1
Pages:	4 (including cover)

Please acknowledge the receipt of this addendum by signing and faxing back to **(419) 691-0241**.

Authorized Signature	Company
Printed Name & Title	Business Address
	City, State, and Zip Code
	Business Phone

Department of Public Service
5330 Seaman Road
Oregon, Ohio 43616
(419) 698-7047
FAX (419) 691-0241

November 19, 2018

ADDENDUM No. 1
Annual Waterline Replacement – Homestead Subdivision and Worden Road

CITY OF OREGON
DEPARTMENT OF PUBLIC SERVICE

BIDS TO BE OPENED: Tuesday, November 27, 2018 at 10:00 A.M.

Plan holders of the City of Oregon's Annual Waterline Replacement – Homestead Subdivision and Worden Road are hereby notified of the following amendments to the Contract Documents. The following additions, alterations, deletions and/or clarifications shall be part of the Base Bid as much as if they were originally included in the Contract Documents. This Addendum No. 1 is hereby made a part of the Contract Documents.

CONTRACT CHANGES

1) **INFORMATION TO BIDDERS – PAGE 5**

Replace Engineer's Estimate $1,193,000 with ***$1,220,000***

2) **PROJECT BID FORM**

Replace BID FORM PAGE 9 with the attached **REVISED BID FORM PAGE 9, DATED 11/19/18**

The revisions are as follows:

The estimated quantity for Item 10 – 8" Waterline, C900, Type B was changed to 5122 LF. This change is to reflect waterline installed at driveway locations

The estimated quantity for Item 11 – 8" Waterline, C900, Type C was changed to 4595 LF.

3) **PLAN SHEET – PAGE 12 OF 32**

On Page 12 of 32, the plan view callout, "STA 14+00.02, 13.24, 8" X 8" TAPPING SLEEVE, VALVE, VALVE MANHOLE, EXCAVATION AND RESTORATION (CITY OF OREGON WATER DEPT. – TO MAKE TAP) CONTRACTOR SHALL COORDINATE WORK WITH WATER DEPT."

Should be replaced with:

"STA 14+00.02, 13.24, 8" X 8" TAPPING SLEEVE, VALVE, VALVE BOX, EXCAVATION AND RESTORATION (CITY OF OREGON WATER DEPT. – TO MAKE TAP) CONTRACTOR SHALL COORDINATE WORK WITH WATER DEPT."

Department of Public Service
5330 Seaman Road
Oregon, Ohio 43616
(419) 698-7047
FAX (419) 691-0241

4) **PLAN SHEET – PAGE 15 OF 32**

On Page 15 of 32, the plan view callout, "STA 13+99.76, 39.92, 8" X 8" TAPPING SLEEVE, VALVE, VALVE MANHOLE, EXCAVATION AND RESTORATION (CITY OF OREGON WATER DEPT. – TO MAKE TAP) CONTRACTOR SHALL COORDINATE WORK WITH WATER DEPT."

Should be replaced with:

"STA 13+99.76, 39.92, 8" X 8" TAPPING SLEEVE, VALVE, VALVE BOX, EXCAVATION AND RESTORATION (CITY OF OREGON WATER DEPT. – TO MAKE TAP) CONTRACTOR SHALL COORDINATE WORK WITH WATER DEPT."

5) **PLAN SHEET – PAGE 21 OF 32**

On Page 21 of 32, the plan view callout, "STA 12+40.87, 26.10 PROP 8" GATE VALVE & VALVE BOX"

Should be replaced with:

"STA 12+40.87, 26.10 PROP HYD ASSEMBLY"

6) **PLAN SHEET – PAGE 23 OF 32**

On Page 23 of 32, the plan view callout, "STA 7+39.19, -24.03 PROP 8" GATE VALVE & VALVE BOX"

Should be replaced with:

"STA 7+39.19, -24.03, PROP HYD ASSEMBLY"

7) **PLAN SHEET – PAGE 26 OF 32**

On Page 26 of 32, the plan view callout, "STA 7+42.79, 308.97 PROP 8" GATE VALVE & VALVE BOX"

Should be replaced with:

"STA 7+42.37, -21.92, PROP HYD ASSEMBLY"

Paul Roman, P.E.
Director of Public Service

BID FORM

PROJECT: ANNUAL WATERLINE REPLACEMENT – HOMESTEAD SUBDIVISION AND WORDEN ROAD - 2018

To the Director of Public Service
Municipal Building
5330 Seaman Road
Oregon, Ohio 43616

I. The undersigned, having familiarized _____ with the local conditions affecting the cost of the work and with the Contract Documents, hereby proposes to perform everything required to be performed and to provide and furnish all of the labor, materials, necessary tools, expendable equipment, and all utility and transportation services necessary to perform and complete in a workmanlike manner all of the work required for the installation of 10,000 LF of 8" waterline, fire hydrants, valves and appurtenances, restoration, etc., for the CITY OF OREGON, OHIO, all in accordance with the specifications for the following prices, to wit:

GENERAL – WATERLINE BASE BID

REF NO.	ODOT ITEM#	ITEM DESCRIPTION	ESTIMATED QUANITY	UNIT	UNIT PRICE BID	TOTAL AMOUNT BID
		General Requirements				
1	201	Clearing and Grubbing	1	LS		
2	614	Maintenance of Traffic	1	LS		
3	623	Construction Layout Staking	1	LS		
4	SPEC	Restoration of Right-of-Way	1	LS		
5	SPEC	Bid and Performance Bond	1	LS		
		Erosion and Sediment Control				
6	SPEC	Construction Seeding and Mulching	175	SY		
7	SPEC	Perimeter Filter Fabric Fence	50	LF		
8	SPEC	Inlet Protection	25	EA		
9	SPEC	Construction Entrance	8	CY		
		Waterline				
10	638	8" Waterline, C900, Type B	**5122**	LF		
11	638	8" Waterline, C900, Type C	**4595**	LF		
12	638	8" Waterline, By Trenchless Method	287	LF		
13	638	8" Gate Valve with Valve Box	17	EA		