



City of Opportunity

Department of Public Service  
5330 Seaman Road  
Oregon, Ohio 43616  
(419) 698-7047  
FAX (419) 691-0241

February 5, 2019

**ADDENDUM No. 2**

**LUC – OLD MILLARD AVENUE BRIDGE  
PID 100394**

**CITY OF OREGON  
DEPARTMENT OF PUBLIC SERVICE**

**BIDS TO BE OPENED: Tuesday, February 12, 2019 at 10:00 AM**

Plan holders of the City of Oregon’s LUC – Old Millard Avenue Bridge are hereby notified of the following amendments to the Contract Documents. The following additions, alterations, deletions and/or clarifications shall be part of the bid specifications as much as if they were originally included in the Contract Documents. This Addendum No. 2 is hereby made a part of the Contract Documents.

**THE FOLLOWING PLAN SHEET HAS BEEN UPDATED AND IS ATTACHED:**

**Replace General Notes Sheet 5 of 40 with updated sheet dated 2/4/19.**

- Environmental Commitment Note #9 has been revised
- ITEM SPECIAL - TESTING AND DISPOSAL OF CONTAMINATED SOIL - note has been revised.

**\* \* \* END OF ADDENDUM NO. 2 \* \* \***

A handwritten signature in blue ink, appearing to read "Paul Roman".

Paul Roman, P.E  
Director of Public Service

\\tts008fs\projects\15285\200-15285-1600\CAD\100394\_OLD\MILLARD\_BR\Design\Roadway\Sheets\00394\_GN002.dgn Sheet 2/4/2019 3:52:30 PM dave.charville

**ENVIRONMENTAL COMMITMENT NOTES**

THE CONTRACTOR SHALL COMPLY WITH THE FOLLOWING ENVIRONMENTAL COMMITMENTS ESTABLISHED FOR THE PROJECT:

1. ALL WORK SHALL BE PERFORMED WITHIN THE EXISTING AND TEMPORARY RIGHT OF WAY.
2. ADJACENT PROPERTY OWNERS SHALL HAVE ACCESS TO THEIR PROPERTIES DURING CONSTRUCTION.
3. THE CONTRACTOR SHALL COMPLY WITH THE MAINTENANCE OF TRAFFIC NOTES AND CONSTRUCTION PHASING PER THE PLANS. THE CONTRACTOR SHALL COORDINATE WITH THE CITY OF OREGON AND OTHER LOCAL GOVERNMENTS, IF NECESSARY, FOR THE ESTABLISHMENT OF APPROPRIATE LOCAL DETOUR ROUTES, AND TO ACCOMMODATE ANY AND ALL LOCAL SPECIAL EVENTS OR FESTIVALS.
4. THE CONTRACTOR SHALL PROVIDE THE CITY OF OREGON WITH WRITTEN NOTICE OF ANY DETOUR, LANE CLOSURES, AND OTHER CONSTRUCTION RELATED ACTIVITIES THAT WOULD CAUSE INCONVENIENCES TO THE TRAVELING PUBLIC. THE WRITTEN NOTICE SHALL BE PROVIDED A MINIMUM OF 21 CALENDAR DAYS IN ADVANCE SO THAT THE GENERAL PUBLIC, LOCAL EMERGENCY SERVICES AND OFFICIALS, INCLUDING POLICE, FIRE, AND LOCAL SCHOOLS CAN BE INFORMED AND UPDATED ON THE PROJECT CONSTRUCTION DETAILS BY THE CITY OF OREGON THROUGH THE USE OF PRESS RELEASES TO LOCAL MEDIA OUTLETS.
5. THE CONTRACTOR SHALL NOT REMOVE ANY TREES UNDER THIS PROJECT FROM APRIL 1 THROUGH SEPTEMBER 30. THE PROJECT IS LOCATED WITHIN THE KNOWN HABITAT RANGES OF THE FEDERALLY LISTED AND PROTECTED INDIANA BAT AND NORTHERN LONG-EARED BAT. ALL NECESSARY TREE REMOVAL SHALL OCCUR FROM OCTOBER 1 THROUGH MARCH 31. THIS REQUIREMENT IS NECESSARY TO AVOID AND MINIMIZE IMPACTS TO THESE SPECIES AS REQUIRED BY THE ENDANGERED SPECIES ACT. FOR THE PURPOSES OF THIS NOTE, A TREE IS DEFINED AS A LIVE, DYING, OR DEAD WOODY PLANT, WITH A TRUNK THREE INCHES OR GREATER IN DIAMETER AT A HEIGHT OF 4.5 FEET ABOVE THE GROUND SURFACE, AND WITH A MINIMUM HEIGHT OF 13 FEET.
6. THE PROJECT IS LOCATED WITHIN THE KNOWN HABITAT RANGE OF THE KIRTLAND'S WARBLER. TO MINIMIZE IMPACTS TO THE KIRTLAND'S WARBLER DURING MIGRATION, TREES AND BRUSH SHALL NOT BE REMOVED BETWEEN APRIL 22ND AND JUNE 1ST OR BETWEEN AUGUST 15TH AND OCTOBER 15TH. IF THIS SPECIES IS ENCOUNTERED WITHIN THE CONSTRUCTION LIMITS DURING CONSTRUCTION OPERATIONS, ALL CONSTRUCTION OPERATIONS WILL CEASE AND THE PROJECT ENGINEER SHALL IMMEDIATELY CONTACT THE ODOT-OES AT 614-466-7100, WHO WILL IMMEDIATELY CONTACT THE USFWS COLUMBUS FIELD OFFICE. CONSTRUCTION ACTIVITIES SHALL NOT CONTINUE UNTIL THIS ADDITIONAL COORDINATION/CONSULTATION WITH USFWS IS CONCLUDED.

7. THE CONTRACTOR IS NOT AUTHORIZED TO PLACE ANY FILL IN OR WORK WITHIN ANY WETLAND OR WATERWAY BELOW THE ORDINARY HIGH WATER MARK (OHWM) OF ANY STREAM, INCLUDING OTTER CREEK, DURING CONSTRUCTION.

8. THE CONTRACTOR SHALL CERTIFY IN WRITING TO THE ENGINEER WITHIN 3 WEEKS AFTER CONTRACT EXECUTION THAT THE CONTRACTOR HAS PREPARED A SITE SPECIFIC HEALTH AND SAFETY PLAN (SSHSP) IN ACCORDANCE WITH OSHA 29 CFR PART 1910.120 FOR OPERATIONS INVOLVING HAZARDOUS SUBSTANCES RELATED TO THE FORMER WESTOVER LANDFILL. THE CONTRACTOR SHALL MAKE THE SSHSP AVAILABLE AT THE PROJECT SITE.

9. ENVIRONMENTAL STUDIES HAVE SHOWN THAT THERE IS A POTENTIAL OF ENCOUNTERING ARSENIC, LEAD, BENZOPYRENE, AND CHROMIUM CONTAMINATED SOIL AND/OR OTHER REGULATED SUBSTANCES DURING EXCAVATIONS FOR CONSTRUCTION ACTIVITIES NEAR THE FORMER WESTOVER LANDFILL AT 1100 YORK STREET (LUCAS COUNTY PARCEL #44-06997). ANALYTICAL RESULTS FOR A SOIL SAMPLE COLLECTED FOR CLOSED WESTOVER LANDFILL AT STA. 16+88, 38' RT ARE AVAILABLE FROM THE CITY OF OREGON FOR REVIEW. ANY SOIL EXCAVATED IN THE VICINITY OF THE SOIL BORING SHALL BE REUSED ON SITE, IN THE VICINITY OF THE BORING. ANY EXCAVATED SOIL IN THE VICINITY OF THE BORING WHICH CANNOT BE REUSED ON SITE MUST BE PROPERLY CONTAINERIZED, TESTED, AND DISPOSED BY THE CONTRACTOR AS A SOLID WASTE AT A LICENSED SOLID WASTE DISPOSAL FACILITY.

10. THE CONTRACTOR SHALL NOTIFY ALL INVOLVED UTILITY COMPANIES AT LEAST FIVE (5) WORKING DAYS BEFORE ANY CONSTRUCTION WORK IS PERFORMED. THE CONTRACTOR SHALL NOTIFY THE OHIO UTILITIES PROTECTION SERVICE (OUPS) AT LEAST TWO WORKING DAYS PRIOR TO COMMENCING WORK, AT (800) 362-2764.

THE CONTRACTOR SHALL COOPERATE WITH ALL UTILITIES LOCATED WITHIN THE LIMITS OF THIS PROJECT AND TAKE RESPONSIBILITY FOR THE PROTECTION OF THE UTILITY PROPERTY AND SERVICES. THE CONTRACTOR SHALL EXERCISE CAUTION WHEN WORKING IN PROXIMITY TO THE EXISTING AND/OR RELOCATED UTILITY FACILITIES. THE CONTRACTOR SHALL FIELD LOCATE ALL EXISTING UTILITIES, INCLUDING BUT NOT LIMITED TO WATERLINES, OIL PIPE LINES, GAS LINES, ELECTRICAL LINES, TELEPHONE LINES, CABLE LINES AND COORDINATE WITH THE PROPER UTILITY COMPANY REPRESENTATIVES TO PROVIDE SUPPORT OF ANY LINES DURING CONSTRUCTION TO ENSURE LINES ARE KEPT IN SERVICE AT ALL TIMES.

11. THE CONTRACTOR SHALL PROVIDE ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES THROUGHOUT THE DURATION OF THE PROJECT, AS NECESSARY, IN ACCORDANCE WITH THE OHIO EPA GENERAL PERMIT NO. OHC000005, EFFECTIVE APRIL 23, 2018, AUTHORIZATION FOR STORM WATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITY UNDER THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE ODOT SUPPLEMENTAL SPECIFICATION 832 AND THE SPECIFICATIONS SET FORTH IN THE CONSTRUCTION PLANS FOR THIS PROJECT AND SHALL CONFORM TO THE MOST CURRENT VERSION OF ODOT'S CONSTRUCTION AND MATERIAL SPECIFICATIONS, LOCATION AND DESIGN MANUAL, AND ODOT STANDARD DRAWINGS TO ENSURE ADEQUATE EROSION AND SEDIMENT CONTROL DURING CONSTRUCTION. ANY DISTURBED AREAS SHALL BE RESEED TO ESTABLISH AND MAINTAIN ADEQUATE PROTECTIVE VEGETATION.

**ITEM SPECIAL - TESTING AND DISPOSAL OF CONTAMINATED SOIL**

ENVIRONMENTAL STUDIES HAVE SHOWN THAT THERE IS A POTENTIAL OF ENCOUNTERING ARSENIC, LEAD, BENZOPYRENE, AND CHROMIUM CONTAMINATED SOIL AND/OR OTHER REGULATED SUBSTANCES DURING EXCAVATIONS FOR CONSTRUCTION ACTIVITIES NEAR THE FORMER WESTOVER LANDFILL AT 1100 YORK STREET (LUCAS COUNTY PARCEL #44-06997). ANALYTICAL RESULTS FOR A SOIL SAMPLE COLLECTED FOR CLOSED WESTOVER LANDFILL AT STA. 16+88, 38' RT ARE AVAILABLE FROM THE CITY OF OREGON FOR REVIEW.

ANY SOIL EXCAVATED IN THE VICINITY OF THE SOIL BORING AT STA. 16+88, 38' RT SHALL BE REUSED ON SITE, IN THE VICINITY OF THE BORING AT THE DIRECTION OF THE CITY. ANY EXCESS EXCAVATED SOIL IN THE VICINITY OF THIS BORING WHICH CANNOT BE REUSED ON SITE SHALL BE PROPERLY CONTAINERIZED, TESTED, AND DISPOSED BY THE CONTRACTOR AS A SOLID WASTE AT A LICENSED SOLID WASTE DISPOSAL FACILITY AT THE DIRECTION OF THE CITY.

THE FOLLOWING ESTIMATED QUANTITY HAS BEEN INCLUDED IN THE GENERAL SUMMARY FOR CONTAINERIZING, TESTING, AND DISPOSING OF THE SOIL AS A SOLID WASTE AT THE DIRECTION OF THE CITY OF OREGON.

ITEM SPECIAL - TESTING AND DISPOSAL OF CONTAMINATED SOIL  
80 TON

▲ 2/4/19

▲ 2/4/19

▲ - Addendum #2